



**Miracle League Field Base:**

- Install the field base using either concrete or asphalt. Concrete should have a light (fine) broom finish.
- Asphalt has proven to provide the best performance as concrete is subject to cracking and heaving which can cause cracking in the EverTop surface which would not be covered under warranty.
- A photo of the concrete or asphalt needs to be sent to FlexGround at the time of finish pour as this will start the clock as to when the installation can be scheduled.
- Assure the subbase is properly prepared as not to cause settling or major cracking.
- FlexGround does not make recommendations on the concrete or asphalt thickness due to each region having different soil conditions. Please contact your local asphalt or concrete companies for this information.
- The concrete or asphalt must have a 1-2 percent pitch to drain water off the surface to avoid mold due to standing water. No greater than a 1/8 deep birdbath in a 6ft diameter will be accepted.
- All fields must be water tested, often provided by the local fire department.
- Please provide post flood photos and have Miracle League/GC signoff that the drainage was sufficient, and bird bathing as described above was not present.
- Cure time for concrete is 7 days minimum and requires acid wash and rinse. The acid wash and rinse will be done by the general contractor.
- Cure time for asphalt is 30 days minimum and the surface must be flooded prior to scheduling installation.
- Water and electricity must be available and accessible on site for the installer.